

ALAMEDA COUNTY
CONGESTION MANAGEMENT AGENCY

1333 BROADWAY, SUITE 220 • OAKLAND, CA 94612 • PHONE: (510) 836-2560 • FAX: (510) 836-2185
E-MAIL: mail@accma.ca.gov • WEB SITE: accma.ca.gov

ADDENDUM NO. 3

**UPTOWN TRANSIT PROJECT
PROJECT NO. 06-05**

December 23, 2005

Dear Contractor:

This addendum is being issued to the contract for the Uptown Transit Project, Project No. 06-05.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on **Thursday, January 19, 2006 at 2 P.M. (PST).**

This addendum is being issued to revise the Notice to Contractors, Special Provisions, Proposal and Contract. The following items indicate additions and/or deletions to the above referenced documents, and are hereby made a part thereof and are subject to all applicable requirements hereunder as if originally shown and/or specified.

The documents of this project are hereby changed as follows:

I. Special Provisions

- 1) Title Sheet – Revise Bid Opening Date to **Thursday, January 19, 2006, 2:00 P.M. (PST).**
- 2) Notice to Contractor – Change Bid Opening date in first paragraph to 2:00 PM (PST), Thursday, January 19, 2006.
- 3) Section 10-4, “Relocate Utilities and Adjust To Grade” – Change entire seventh paragraph starting with “Where existing manhole to remain occurs at the new curb location ...” to read:

“Where existing manhole to remain occurs at the new curb location (as indicated on the Contract Drawings), furnish and install removable curb plate. Removable curb plate shall consist of a hinged lid formed to complete the sidewalk and curb at the manhole location and allow access to the manhole. Removable curb plate dimensions: Size A: Inside depth: 48 inches. Inside width: 54 inches. Size B: Inside depth: 12 inches. Inside width: 54 inches. (Note, depth dimension is measured



ALAMEDA COUNTY CONGESTION MANAGEMENT AGENCY

1333 BROADWAY, SUITE 220 • OAKLAND, CA 94612 • PHONE: (510) 836-2560 • FAX: (510) 836-2185
E-MAIL: mail@accma.ca.gov • WEB SITE: accma.ca.gov

perpendicular to curb and width is measured parallel to curb.) Removable curb plate shall be reinforced to support AASHTO H-20 wheel load with a maximum deflection of 1/150th of the span and shall be as manufactured by Madruga Iron Works, Inc, (209) 843 7003, or equal, and shall consist of a single lockable, reinforced, and hinged lid and lid stay (hold-open arm). Manufacturer to provide structural calculations stamped by registered engineer upon request. Sides and backs shall reduce the need for formwork and be provided with anchors to tie to adjacent sidewalk. Removable curb plate shall be fabricated from steel and galvanized; exposed surfaces shall have non-slip finish. Submit shop drawings and installation instructions.

- 4) Section 10-10.03, "Payment" – Change entire third paragraph starting with "The contract unit price paid for " Modified Type B Curb and Gutter" shall include ..." to read:


" The contract unit price paid for " Modified Type B Curb and Gutter" shall include full compensation for furnishing all labor, materials, tools, equipment, hauling and stockpiling and incidentals, for all the work in installation of curb and gutter, including grading details for curb plate cut-outs, aggregate base, base compaction, dowels, complete-in-place as shown on the Plans, as specified in the Standard Specifications, these Special Provisions and as directed by the Engineer, and no additional compensation shall be allowed therefor."

II. Plans

- 1) Add the attached Drawing No. A02 "Grading Details for Curb Plate Cut Outs" to the Contract Plans.
- 2) Drawing No. C4 – Delete drawing in its entirety and replace with the attached Drawing No. C4, Addendum No. 3.

III. Proposal Forms

- 1) Replace the Bid List with the attached Bid List, Pages 1 and 2, identified as Addendum No. 3.



ALAMEDA COUNTY
CONGESTION MANAGEMENT AGENCY

1333 BROADWAY, SUITE 220 • OAKLAND, CA 94612 • PHONE: (510) 836-2560 • FAX: (510) 836-2185
E-MAIL: mail@accma.ca.gov • WEB SITE: accma.ca.gov

To Proposal and Contract book holders:

- Indicate receipt of this addendum by completing the addenda certification form in your proposal.
- Replace the Bid List with the attached forms.
- Submit bids in the Proposal and Contract book you now possess.
- Inform subcontractors and suppliers as necessary.

If you are not a Proposal and Contract book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

This office is sending this addendum via fax and mail to Proposal and Contract book holders to ensure that each receives it.

Sincerely,

A handwritten signature in black ink, appearing to read "Frank Furger", written over a horizontal line.

FRANK FURGER, DEPUTY DIRECTOR
Alameda County Congestion Management Agency

Attachments: Drawing No. A02
Drawing No. C4
Revised Bid List

END OF ADDENDUM NO. 3

BID LIST

UPTOWN TRANSIT CENTER PROJECT
Project No. 06-05

Base Bid

Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total
1.	Construction waste management	1	LS		
2.	Progress schedule (critical path method)	1	LS		
3.	Traffic control system	1	LS		
4.	Coordination with City	1	LS		
5.	Coordination with TWTC	1	LS		
6.	Coordination with SBC	1	LS		
7.	Coordination with PG&E	1	LS		
8.	Coordination with EBMUD	1	LS		
9.	Coordination with AboveNet	1	LS		
10.	Coordination with BART	1	LS		
11.	Mobilization	1	LS		
12.	Demolition	1	LS		
13.	Trench for PG&E gas line	1	LS		
14.	Adjust sanitary sewer manhole to grade	3	EA		
15.	Adjust water valve cover to grade	7	EA		
16.	Adjust gas valve cover to grade	4	EA		
17.	Adjust water monitoring well cover to grade	1	EA		
18.	Adjust AboveNet manhole to grade	1	EA		
19.	Removable curb plate	1	EA		
20.	Sidewalk elevator frame and door	1	EA		
21.	Roadway excavation	335	CY		
22.	AC patch	1050	SF		
23.	AC base	316	CY		
24.	PCC road pavement	16130	SF		
25.	PCC cross walks with architectural finish	950	SF		
26.	PCC sidewalk	9894	SF		
27.	PCC sidewalk with arch. finish to match (e)	970	SF		
28.	Dark decorative PCC sidewalk	3405	SF		
29.	Modified Type-B curb and gutter	1000	LF		
30.	ADA 'Case E' curb ramp	6	EA		
31.	Driveway	200	SF		
32.	Thickened slab at windscreen	2	EA		
33.	Sealant joint bet. new sidewalk and (e) building	575	LF		

Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total
34.	Type B storm drain inlet structure	2	EA		
35.	Trench Drain	120	LF		
36.	HDPE storm drain 12 in. ID	35	LF		
37.	Pier Foundation for Canopies	12	EA		
38.	Traffic Signage, Stripping, and Markings	1	LS		
39.	Electrical and Telecommunications	1	LS		
40.	Traffic Signal System	1	LS		
41.	Signal Interconnect System	1	LS		
42.	Surveying	1	LS		
43.	Type 1 storm drain manhole	1	EA		
44.	Storm drain concrete culvert	1	EA		
45.	Type B curb and gutter	20	LF		
46.	Modified 4 in. Type B curb and gutter	40	LF		
BASE BID TOTAL					

BID ALTERNATE NO. 1
Delete provisions for canopy or canopies

Item No.	Item Description	Estimated Quantity	Unit	Unit Price	Total
1.	Delete dark decorative PCC sidewalk and substitute PCC sidewalk	1980	SF		
2.	Delete thickened slab at windscreen	2	EA		
3.	Delete pier foundation for canopy	12	EA		
4.	Delete electrical and telecommunications conduit run between hand hole and canopy foundations at each canopy	6	EA		
TOTAL TO BE DEDUCED FROM BASE BID TOTAL					

Write-In (Base Bid Total) _____

Note: All Bid Prices shall be all inclusive including all applicable taxes and all other incidentals.